GOVERNMENT OF TELANGANA
GROUND WATER DEPARTMENT

From
B. Shyam Prasad Naik, M.Sc.,
District Ground Water Officer,
Ground Water Department,
KARIMNAGAR

To
The Tahsildar,
V-Saidapur(M)
KARIMNAGAR

Lr. No. 02/WALTA/T/2018/366 **Date: 26.10.2026**

Sir,

Sub: - Ground Water Department, Karimnagar – TSWALTA - Groundwater Investigations for selection of well site - Furnishing the Report - Reg.

Ref: - Online Application received through TS-iPASS ,
Application No. GWWALT202627231405801 Dt: 03.10.2026

-ooOoo-

The Groundwater Investigations were carried out for selection of Dug well site in the following Beneficiary land Raikal (V) & V-Saidapur (M). The investigation report is herewith enclosed for further necessary action.

Sl. No	*Village*	*Name of the Beneficiary*	*Survey No.*	*Recommended/ Rejected*
1	Raikal-Saidapur(V)	Banothu Ramulu	290/5/2	***Recommended for Dug well***

The above recommended Dug well shall be registered with Mandal WALTA authority after completion of digging.

Encl: Report (1 No).

SD Naik 26/10/2026
DISTRICT GROUND WATER OFFICER,
GWD, KARIMNAGAR

REPORT ON FEASIBILITY OF GROUNDWATER FOR CONSTRUCTION OF DUG WELL/BORE WELL UNDER WALTA

I. GENERAL		
1	Investigation conducted by :	B.Umadevi (AHG)
2	Date and duration of investigation :	16/10/2026
3	Name of the beneficiary/Organization	Banothu Ramulu
4	Purpose of investigation and requirement of water	Irrigation purpose
5	**LOCATION :**	
	Village	Raikal
	Mandal	V-Saidapur
	District	Karimnagar
	Survey No.	290/5/2
	Extent of the area in Ac.	30Gts
	Co-ordinates and distance and direction with reference to village central point	18° 9'48.17"N, 79°18'1.21"E (350m towards South direction from Centre of the village)
II	**PHYSIOGRAPHY AND DRAINAGE :**	
1	Topography	Gentle slope towards South-East direction
2	Soil type and thickness	Red Soil, 1.5-2.0m
3	Drainage pattern	Sub Dendritic
4	Elevation [MSL] in m.	338 m
5	Sub-basin name, categorization and stage of development in the basin	Knr_E_22_Veenavanka_Krmr_Safe_24.10%
6	Average annual rainfall in mm.	Actual Rainfall:1442.7 mm, NormalRainfall: 814.9 mm
7	Tanks/Reservoirs/Canals	-
8	Proximity to surface water bodies	-
9	Stream/River [specify the nature influent/effluent]	-
10	Command / Non Command	Command
III	**HYDROGEOLOGICAL CONDITIONS :**	
1	Geology of the area [Rock type and texture]	Coarse Granites
2	Average thickness of weathered zone	17-20m
3	Structural controls if any	-
4	Depth range of wells in the area in m.	
	1) Dugwell	17-20m
	2) Borewells	-
5	Yield range of wells	
	1) Dugwells [lpd]	60-70 m3/day
	2) Borewells [lph]	
6	Area irrigated under each well kharif/rabi	
	1) Dugwells	1.0-1.5 Acs ID Crops
	2) Bore wells	
7	Location of nearest piezometer,depth to water level in the piezometer and water level trend.	Raikal Pz :- 8.57m (Oct-26)

IV	**Hydrogeological evidence :**							
	Well Inventory [2 Km. Radius from the investigated area] data							
Sl. No	Type of well	Name of the Owner	Dia & depth of well in (m)	SWL in m.bgl.	Mode of lift with HP	Yield in lph & hours of pumping	Cropping pattern and area irrigated in ha. Kharif/ Rabi	Remarks
1	Dug well	Banothu Bitchu	7m & 20m	8.12	3HP	60-65 m3/day	1.0-1.5 acs ID Crops	
2	Dug well	Banothu Ravi	6m & 19m	8.79	3HP	65-70 m3/day	1.0-1.5 acs ID Crops	

V	**RESULTS OF GEOPHYSICAL INVESTIGATIONS :**								
VES No.									Remarks
Hydrogeological survey conducted									

VI	**QUALITY OF GROUND WATER**		Suitable for irrigation
VII	**SUGGESTIONS FOR IMPROVING RECHARGE TO GROUND WATER**		Suggested for construction of Farm Pond in the South East corner of the site(6m*6m*1m) (18° 9'48.14"N, 79°18'1.18"E°)
VIII	**Conclusions & Recommendations :**		
1	Justification for recommending/rejecting the data		Based on hydrogeological survey , the surveyed land is feasible for construction of open well. Hence the site is recommende for open well .
2	If recommended, Type of well recommended with dia and depth		Dug well- dia 6m, depth 20m
3	Location of recommended site with reference to permanent land mark		18° 9'48.17"N, 79°18'1.21"E (22m from South and 10 m from North side of the site)
4	Distance of nearest well		75m
5	Expected yield in lph.		65-70m3/day
6	Expected area to be irrigated and recommended cropping pattern		1.0-1.5 Acs ID Crops
7	Date of submission of report		23/10/2026

IX SKETCH OF THE AREA :



INDEX
- existing open well
O- Recommended open well

B. C
SIGNATURE OF THE INVESTIGATING OFFICERS

District Groundwater Officer,
GWD Karimnagar.