SOUTHERN POWER DISTRIBUTION COMPANY OF T.S. LIMITED

Office of
THE CHIEF GENERAL MANAGER
COMMERCIAL
CORPORATE OFFICE
TSSPDCL
HYDERABAD

S.P.O.O.(COMMERCIAL)MS.NO.263/2023-24, DT.23.02.2024

Sub:- TSSPDCL – COMML – TS-iPASS Estimate for extension of supply to 1No.5130KVA CMD under HT Cat-I at 33KV supply to M/s.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub -division of Medak division- Sanction – Administrative approval Accorded – Reg.

Ref : Estimate Number: E-2023-60-01-11-04-048

The above estimate is administratively approved and technically sanctioned and registered as C.NO.669758, NOTE NO.#10, DT.23.02.2024

The sanction accords is subject to the follwing conditions:

1. TSSPDCL after careful examination of the above proposal hereby accords approval for the scheme at a cost of 32,12,709.65
2. In excercise of the powers conferred under section 42.1 of the Electricity Act,2003 Central Act. No.36 of 2003 it system in his area of supply and to supply electricity in accordance with the provisions contained in this act.
3. The sanction accorded in para-1 above is subject to instructions issued already on release of service and tariff as may be in force from time to time.
4. The expenditure is chargeable to TSSPDCL-Capital Receipts and Expenditure- B, Expenditure-2 Transmission Lines (Including Sub-Stations) 3 Distribution System (Including Sub-Stations) capital works in progress Transmission plant (Extra High Voltage A/C. No.0204) Distribution System (High Voltage A/C. No.0204) Distribution System Medium Voltage (A/C. No.0206) Street Lighting.
5. The work will be executed by THE ASSISTANT DIVISIONAL ENGINEER OPERATION MEDAK SUB-DIVIISON and all necessary approvals and payments must be ensured before release of supply.
6. Consumer has to pay the following charges through a single DD in the Customer Service Center / Integrated Customer Service Center.

Serviceline charges	Rs.	30,81,345.90
Development charges / DTR Cost	Rs.	61,56,000.00
CGST on Development Charges	Rs.	5,54,040.00
SGST on Development Charges	Rs.	5,54,040.00
Initial Consumption Deposit	Rs.	76,95,000.00
Application Fee	Rs.	100.00
CGST on Application Fee	Rs.	9.00
SGST on Application Fee	Rs.	9.00
PTR Cost	Rs.	0.00
Total Amount	**Rs.**	**1,80,40,544.00**

SD/-
DIRECTOR COMMERCIAL

Copy To :
THE ASSISTANT ENGINEER/OPR/AE OP CHINNA SHANKA
THE ASSISTANT DIVISIONAL ENGINEER/OPERATION/MEDAK SUB-DIVIISON
THE DIVISIONAL ENGINEER/OPERATION/MEDAK DIVISION
THE SUPERINTENDING ENGINEER/OPERATION/MEDAK CIRCLE
THE CHIEF GENERAL MANAGER/OPERATION/RURAL ZONE

23/2
DIVISIONAL ENGINEER

Generated on 23-02-2024 (Commercial) by MIS@TSSPDCL, Corporate Office, 6-1-50, Mint Compound Hyd-500 063

SOUTHERN POWER DISTRIBUTION COMPANY OF T.S. LIMITED

Office of
THE CHIEF GENERAL MANAGER
COMMERCIAL
CORPORATE OFFICE
TSSPDCL
HYDERABAD

S.P.O.O.(COMMERCIAL)MS.NO.263/2023-24, DT.23.02.2024

Sub:- TSSPDCL – COMML – TS-iPASS Estimate for extension of supply to 1No.5130KVA CMD under HT Cat-I at 33KV supply to M/s.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub -division of Medak division- Sanction – Administrative approval Accorded – Reg.

Ref : Estimate Number: E-2023-60-01-11-04-048

The above estimate is administratively approved and technically sanctioned and registered as C.NO.669758, NOTE NO.#10, DT.23.02.2024

The sanction accords is subject to the follwing conditions:

1. TSSPDCL after careful examination of the above proposal hereby accords approval for the scheme at a cost of 32,12,709.65
2. In excercise of the powers conferred under section 42.1 of the Electricity Act,2003 Central Act. No.36 of 2003 it system in his area of supply and to supply electricity in accordance with the provisions contained in this act.
3. The sanction accorded in para-1 above is subject to instructions issued already on release of service and tariff as may be in force from time to time.
4. The expenditure is chargeable to TSSPDCL-Capital Receipts and Expenditure- B, Expenditure-2 Transmission Lines (Including Sub-Stations) 3 Distribution System (Including Sub-Stations) capital works in progress Transmission plant (Extra High Voltage A/C. No.0204) Distribution System (High Voltage A/C. No.0204) Distribution System Medium Voltage (A/C. No.0206) Street Lighting.
5. The work will be executed by THE ASSISTANT DIVISIONAL ENGINEER OPERATION MEDAK SUB-DIVIISON and all necessary approvals and payments must be ensured before release of supply.
6. Consumer has to pay the following charges through a single DD in the Customer Service Center / Integrated Customer Service Center.

Serviceline charges	Rs.	30,81,345.90
Development charges / DTR Cost	Rs.	61,56,000.00
CGST on Development Charges	Rs.	5,54,040.00
SGST on Development Charges	Rs.	5,54,040.00
Initial Consumption Deposit	Rs.	76,95,000.00
Application Fee	Rs.	100.00
CGST on Application Fee	Rs.	9.00
SGST on Application Fee	Rs.	9.00
PTR Cost	Rs.	0.00
Total Amount	**Rs.**	**1,80,40,544.00**

SD/-

DIRECTOR COMMERCIAL

Copy To :

THE ASSISTANT ENGINEER/OPR/AE OP CHINNA SHANKA

THE ASSISTANT DIVISIONAL ENGINEER/OPERATION/MEDAK SUB-DIVIISON

THE DIVISIONAL ENGINEER/OPERATION/MEDAK DIVISION

THE SUPERINTENDING ENGINEER/OPERATION/MEDAK CIRCLE

THE CHIEF GENERAL MANAGER/OPERATION/RURAL ZONE

23/2

DIVISIONAL ENGINEER

Generated on 23-02-2024 Commercial, TSSPDCL,
Corporate Office, 6-1-50,
Mint Compound Hyd-500 063

SOUTHERN POWER DISTRIBUTION COMPANY OF T.S LIMITED

From,
THE CHIEF GENERAL MANAGER
COMMERCIAL
CORPORATE OFFICE
TSSPDCL
HYDERABAD

To,
M/S.SRI-RAJ IRON & STEEL
SY NO:777/A1
Chandampet
Chandampet
Medak

LR.NO.CGM(COMML)/SE(C)/DE(C)/ADE-II/AE-II/D.NO.758/2023-24, DT.23.02.2024

Sub:- TSSPDCL – COMML – TS-iPASS Estimate for extension of supply to 1No.5130KVA CMD under HT Cat-I at 33KV supply to M/s.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub -division of Medak division- Sanction – Administrative approval Accorded – Demand Notice - Reg.

Ref No: S.P.O.O.(COMMERCIAL)MS.NO.263/2023-24, DT.23.02.2024

Estimate Number: E-2023-60-01-11-04-048 Reg no. HT99943010

The permission accorded is subjected to the following conditions:

1. The work should be executed by a Licensed Contractor as per the standards of TSSPDCL under supervision of THE ASSISTANT DIVISIONAL ENGINEER OPERATION MEDAK SUB-DIVIISON.
2. The material used in the work should confirm to TSSPDCL specifications.
3. If unforeseen calamities/ accidents occur during the execution of work, the TSSPDCL authorities are not held responsible for such incidents and consequential losses or damages. It is the responsibility of the consumer for any loss of material utilised in completing the work till all the services contemplated in the proposal are released.
4. Major materials like AB Switches, HG Fuse sets, Conductor,Structure steel and other materials should be purchased as per TSSPDCL specifications along with test certificate from TSSPDCL vendor. The bills/voucher of materials purchased along with test certificate should be produced to concerned CSC/ICSC before execution of work.
5. The work will be executed as per the sketch enclosed. The work executed by consumer shall be taken over by the TSSPDCL after statuary inspection by TSSPDCL officials. The installation shall be deemed to the property of TSSPDCL after such takeover.
6. The consumer should provide sealing arrangement for control panel and metering equipment.
7. The consumer shall clear off the dues of UDC/Bill stopped services if any existing in the premises or found at a later date and no court cases pending. If any legal disputes arise electricity supply will be disconnected to the premises.
8. There should not be any 11 KV /LT lines passing through from other source of supply in the proposed premises.
9. Distribution Transformer will be provided by TSSPDCL by collecting the cost of DTR/Development charges whichever is higher, however, in case of auto-generated (TSipass and HT) estimates, transformer is to be procured by consumer.
10. Obtaining CEIG/CEA approval for electrical installing. Obtaining NOC as per requirement of A.P Fire Services act 1999, Multi-storied building regulations.
11. No service connection shall be released for Multi-storied buildings / Complexes greater than 10Mtrs in height unless occupancy certificate from concerned authorities.
12. You are requested to pay an Amount Rs.16946850.00 using the below available options :
    a) In shape of Demand Draft in the Customer Service center / Integrated Customer Service drawn in favour of TSSPDCL Payable at MEDAK and handed over to In charge of C.S.Center/Integrated CS.Center.
    (OR)
    b) By scanning the QR Code using TSSPDCL App
    (OR)
    c) Through web portal - www.tssouthernpower.com, Go To **"Payment against Estimates"** option and give Registration number as input .
    (In case of Estimate with multiple Registrations, Give any one registration as input)
14. D.D must be received to concerned CSC within 60 days from D.D issue date.
15. Payments must be received before 23-05-2024 , If not received existing registration will be cancelled.
16. Work must be completed before 21-08-2024, If not completed you have to forfeit the already paid amount.

DIVISIONAL ENGINEER
(Commercial), TSSPDCL,
Corporate Office, 6-1-50,
Mint Compound Hyd-500 063

SOUTHERN POWER DISTRIBUTION COMPANY OF T.S LIMITED

Description of Demand	Original Demand Notice Amount (In Rs)
Application Fees	100
CGST on Application Fee	9
SGST on Application Fee	9
Supervision Charges	315,587.97
CGST on Supervision charges	28,402.92
SGST on Supervision charges	28,402.92
Security Deposit	7,695,000
Development Charges	6,156,000
CGST on Development Charges	554,040
SGST on Development Charges	554,040
Material Cost	1,508,458.35
Material Cost Storage and Handling	45,253.75
CGST on Material Cost S&H	4,072.84
SGST on Material Cost S&H	4,072.84
Material Cost Contengencies	45,253.75
CGST on Material Contg Charges	4,072.84
SGST on Material Contg Charges	4,072.84
Rounded-off cost	0.98
Total Cost	16,946,850

Note :

**

** In Case DTR is procured by Consumer and total DTR cost is greater than DC, niether DC nor DTR Cost will be collected (Only LT registrations).

** 10% of cost for DTRs procured by consumer is collected as Performance Security Charges. This amount along with Testing charges is to be collected and DD/BG details are to be entered in SAP while releasing the Estimate in JAQ login.

** For works to be executed by Department, DTR is supplied by the Depatrment and no Performance Security Deposit shall be collected.

** Testing charges of Rupees One thousand one hundred and eighty (i.e. Rs 1000 + 18 % GST) is to be collected.

**

** You can pay through QR code Scanner or through RTGS to the following Accounts : Account No.- 52125877177 , Bank Name - SBI BANK, MEDAK IFSC Code - SBIN0020098

*** This is a tentative estimate.The amount to be paid will be finalized after revising the estimate.Final amount will be included or adjusted in first bill after release.*

SD/-

DIRECTOR COMMERCIAL

DIVISIONAL ENGINEER
(Commercial), TSSPDCL,
Corporate Office, 6-1-50,
Mint Compound Hyd-500 063

E-2023-30-01-11-04-048

Reg no. HT99943010

Generated on 23-02-2024 17:59:31 in CGM_COMML login.

Estimate Cost Calculation Sheet

WBS Element : E-2023-60-01-11-04-048 WBS Desc. : E/s to 5130KVA Load to M/s SRI-RAJ IRON

Work Executed by : CONSUMER

Service Connection Estimate : NO

Estimate Plan Cost : 32,12,709.65

CSC Registration Number	Applicant Name	HT / LT	Cat.	Sub-cat. / Volt.	Con. load	Cat.	Con. load	Bl_ Monthly	All Doc. Received	No of Shifts	Exst. load	Exst. Cat	Exst. SD
HT99943010	M/S.SRI-RAJ IRON & STEEL	HT	01	033	5,130				X	3			0

SD Calculation:

CSC Registration Number	Cat.	Cont. load	Tariff S:D	Tariff D.C	Cat.	Cont. load	Tariff S.D	Tariff D.C	No. of Times S.D	No of Shifts	S.D Charges	Development Charges
HT99943010	01	5,130	0500	1200					1	3	7,695,000	6,156,000
Total	00	0									7,695,000	6,156,000

DC Calculation / DTR:

DC as per Load(incl GST) : 72,64,080.00

Final Dev. Charges : 72,64,080.00

Materials to be issued by TSSPDCL:

Sl. No.	Material	Material Description	Quantity	Total Cost
1	ITR30061	33KV 1ph PTs,10 VA Burden 0.2 Class	3	72,259.77
2	ITR30054	33KV Metering CT's 100/1A, 0.2S Class	3	51,106.8
3	MHT30071	33KV HT TVR, 100/1A 0.2S 15min IP-Cat C	1	7,997.18

SLC (Refundable Deposit)/ Materials issued from Stores as per the payments to be made by the Customer (including 6%):

Sl. No	Material	Material Description	Quantity	Unit Price	Total Price
1	CBP00001	LT PVC Cu Contr Cable 2 Core 2.5 Sq. mm	100	61.52	6,152.00
2	CDR00010	ACSR Conductor Panther	10	245.63	2,456.30
3	INS30007	33KV Polymer Insulators (B&S)	18	486.68	8,760.24
4	LAS00004	33KV Lightning Arrestors Station Type	3	4,043.77	12,131.31
5	HWR00004	33KV Metal parts(B&S)	18	245.13	4,412.34
6	CDR00004	AAA conductor 100 Sq. mm	5,500	90.56	4,98,080.00
7	SCB10114	33KV 3X400 Heat Shble out/d end ter kit	4	5,341.67	21,366.68
8	INS30008	33KV Polymer Pin Insulators With GI Pins	72	808.73	58,228.56
9	CDR00010	ACSR Conductor Panther	100	245.63	24,563.00
10	BRK30019	33KV 24V FED VCB WITH CTS & CR PANEL	1	4,94,522.38	4,94,522.38
11	INS30007	33KV Polymer Insulators (B&S)	18	486.68	8,760.24
12	CBP00002	LT PVC Cu Contr Cable 4 Core 2.5 Sq. mm	100	101.37	10,137.00
13	INS10005	11KV Guy Insulators (HT)	4	60.11	240.44
14	HWR00004	33KV Metal parts(B&S)	2	245.13	490.26
15	CBX30001	33KV XLPE Cable 3 Core 400 Sq. mm	80	3,841.22	3,07,297.60
16	CBP00006	LT PVC Cu Contr Cable 10 Core 2.5 Sq. mm	200	254.30	50,860.00
	Total				15,08,458.35
	3% S&H Ch.	3% Storage & Handling Charges			45,253.75
	3% Contgs.	3% Contingencies			45,253.75
	G.Total				15,98,965.85
	9% CGST-S&H Ch.	9% CGST on Storage & Handling Charges			4,072.84
	9% SGST-S&H Ch.	9% SGST on Storage & Handling Charges			4,072.84
	9% CGST-Cont.	9% CGST on Contingencies			4,072.84
	9% SGST-S&H Ch.	9% SGST on Contingencies			4,072.84

Incidental Charges Calculation :

Gross Cost of the Estimate : 32,12,709.65

GST on Services : 56,829.95

18% GST on Road Cutting Charges : 0.00

Estimate Cost Calculation Sheet

WBS Element	:		WBS Desc. :	E/s to 5130KVA Load to M/s SRI-RAJ IRON
Work Executed by	:	CONSUMER		
Service Connection Estimate	:	NO		
Estimate Plan Cost	:	32,12,709.65		
Total (Gross cost - GST charges)		:	31,55,879.70	
Incidental Charges		:	**3,15,587.97**	
CGST Incidental charges		:	28,402.92	
SGST Incidental charges		:	28,402.92	

Description of Demand

Application Fees	100
CGST on Application Fee	9
SGST on Application Fee	9
Supervision Charges	315,587.97
CGST on Supervision charges	28,402.92
SGST on Supervision charges	28,402.92
Security Deposit	7,695,000
Development Charges	6,156,000
CGST on Development Charges	554,040
SGST on Development Charges	554,040
Material Cost	1,508,458.35
Material Cost Storage and Handling	45,253.75
CGST on Material Cost S&H	4,072.84
SGST on Material Cost S&H	4,072.84
Material Cost Contengencies	45,253.75
CGST on Material Contg Charges	4,072.84
SGST on Material Contg Charges	4,072.84
Rounded-off cost	0.98
Total Cost	16,946,850

Note : Material cost is calculated based on Plan cost and Moving average cost - whichever is higher on the date of approval.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

D.No :LR.NO.CGM(COMML)/SE(C)/DE(C)/ADE-II/AE-II/D.NO.758/2023-24, DT.23.02.2024

E/s to 5130KVA Load to M/s SRI-RAJ IRON & STEEL PRODUCTS PVT LTD

Ts-I pass Estimate for extension of supply to 1No.5130KVA CMD under HT Cat-I at 33KV supply to M/S.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub-division of Medak division-Under Ts ipass scheme.

Report to Accompany the Estimate

1) General:The proposal is for extension of supply to 1No.5130kva CMD under HT Cat-I at 33KV supply to M/S.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub-division of Medak division-Under Ts ipass scheme.

2) POINT OF SUPPLY:- The 33 KV extended from 132/33KV Chinna Shankarampet Sub Station with dedicated feeder as shown in the Sketch.

MAIN FUTURE OF THE SCHEME:-The proposals involves the following

1. Erection of 1.2 KM 33KV line with 100 Sqmm AAA conductor over existing 11Mtr PSCC pole with a span of 50 Mtrs as dedicated feeder
2. Erection of 0.6 KM 33KV line with 100 Sqmm AAA conductor over existing M+6 towers at span of 100 Mtrs as dedicated feeder
3. Erection of HT structure along with 1No.33KV VCB with Control panel at consumer end
4. Erection of metering equipment
5. Erection of 4 NO.11Mts intermediate poles on 33KV Suraram feeder for road crossing.

POWER TRANSFORMER CAPACITY: The power transformer capacity at 33/11KV Substation at 132/33KV Chinna Shankarampet is 1X50 MVA+1x10/16MVA

The Power Transformer capacity is quite adequate to cater the proposed as well as existing loads only after completion of 132kv Narsapur-Veldurthy DC lie which is under progress vide reference number Lr No.: CE/RZ/HYD/DE(T)ADE(T)/AE(T)-II/F/DNo. 3912/23 dt : 17.01.24.

HT REGULATION:-The tail end HT regulation has calculated and to be within Permissible limits.

Justification: extension of supply to 1No.5130KVA CMD under HT Cat-I at 33KV supply to M/S.SRI-RAJ IRON & STEEL PRODUCTS PVT LTD(UNIT-II) (TS-Ipass)Sy No.777/A1 at Chandampet village in Chinna Shankarampet Section of Medak Sub-division of Medak division-Under Ts ipass scheme.estimate was prepared for sanction please.,HT99943010

Division	**: DE/OP/MEDAK**	**Section**	**: AE OP CHINNA SHANKA**
Project Type	**: SC-Extension of Supply (HT-33KV)**	**Cost Center**	**: 160111401**
Estimate No.	**: E-2023-60-01-11-04-048**	**Estimate Description**	**: E/s to 5130KVA Load to M/s SRI-RAJ IRON**
Network No.	**: 520000561949**	**Estimate Created Date**	**: 01.02.2024**
Reservation No.	**: 8002510054**	**Plant**	**: 1050**
User Status	**: CGMZ NBGD PAPR**	**System Status**	**: CRTD AVAC**
Estimate Approved date	**: 23.02.2024**	**Estimate Sanctioned By**	**: CGM_COMML**

Work to be executed by : CONSUMER

CSC Ren no.	Appl. Name	HT/ LT	Cat. 1	Sub. Cat.1	C.L1	Cat. 2	Sub_ cat.2	C.L2	Bi-Mon.	Doc. Rec.	Ser. Con.	Exst. Load
HT99943010	M/S.SRI-RAJ IRON & STEEL	HT	01	033	5,130.00	00	00	0.00		X		0.00

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

	Estimate Cost (Gross - Including 10% MPV	3457571.52
	Estimate Cost (Gross - Without 10% MPV)	3212709.65
	Less Credits :	0.00
	Estimate Cost (Net - Without 10% MPV) :	3212709.65
	10% Incidental Charges to be collected :	340074.157
Sl.No.	**Proposals involves**	**Total in Rs.**
1	10 - 33KV Line Material	1111010.6506
2	30 - HT Metering Structure at Consumer End	2346560.865

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

Activity No : 10 **Activity Description :** 33KV Line Material

S.No	Materials Code	Materials Text	Item Catagory	Quantity	Unit	Rate in Rs.	Amount in Rs.
1	CDR00010	ACSR Conductor Panther	Stock item	10.000	M	245.63	2,456.30
2	MST00012	MS Channel 100x50 mm	Stock item	600.000	KG	66.79	40,074.00
3	INS30007	33KV Polymer Insulators (B&S)	Stock item	18	EA	486.68	8,760.24
4	HWR00004	33KV Metal parts(B&S)	Stock item	18	SET	245.13	4,412.34
5	FBR30001	33KV M.S.Back Clamps	Stock item	48	SET	283.92	13,628.16
6	CDR00004	AAA conductor 100 Sq. mm	Stock item	5,500.000	M	90.56	498,080.00
7	INS30008	33KV Polymer Pin Insulators With GI Pins	Stock item	72	EA	808.73	58,228.56
8	PLS00004	PSCC Poles 9.1 Mts 280Kgs	Stock item	2	EA	4,259.10	8,518.20
9	FBR30002	33KV M.S.Stay Clamps	Stock item	8	SET	494.93	3,959.44
10	FBR30009	33KV MS Stay Sets without BasePlate	Stock item	4	SET	1,195.17	4,780.68
11	WRS00006	G.I.Stay Wire 7/3.15mm (10SWG)	Stock item	90.000	KG	92.80	8,352.00
12	PLS00013	PSCC Poles 11 Mts 365 Kgs	Stock item	8	EA	6,844.00	54,752.00
13	FBR30004	33KV "V"Cross Arms without Clamps	Stock item	48	EA	1,748.94	83,949.12
14	INS10005	11KV Guy Insulators (HT)	Stock item	4	EA	60.11	240.44
						Material Cost	790,191.48

S.No	Services Code	Services Text	Item Catagory	Quantity	Unit	Rate in Rs.	Amount in Rs.
1	SMR11488	S-GI Bolts & Nuts,Washers etc.,	-	100.000	KG	117.50	11,750.00
2	SWR21190	Excavate-StayPit .45x.45x1.34mSoil ex Hr	-	4	EA	520.00	2,080.00
3	SWR10978	Errection of 11 M long PSCC pole	-	8	EA	4,165.28	33,322.24
4	SWR10107	EXCAVATION OF PIT (2.6" x 2.6" x 6.0")	-	8	EA	700.00	5,600.00
5	SWR11180	SubTrnsprt 11M PSCC Pole incl. L&UL<10KM	-	8	EA	431.97	3,455.76
6	SWR10152	TRANSPORT OF STEEL MATERIAL 80 TO 100KM	-	1.000	TO	787.44	787.44
7	SWR10981	Horizontal Cut point for 33 KV line	-	6	EA	1,759.50	10,557.00
8	SWR10354	Assembly and erection of Stay set 33kv	-	4	SET	684.53	2,738.12
9	SWR10366	Stringing 100sqmm 33/11kv Line 3 Cond SC	-	1.800	KM	12,600.06	22,680.11
10	SWR11083	Erec of 9.1 Mts PSCC poles for	-	2	EA	2,400.00	4,800.00

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

stuts	
Service Cost	97,770.67
GST 18%	17,598.72
3 % S & H Charges :	23705.74
3 % Contingencies on materials:	23705.74
10 % Estt. & General Charges :	79019.15
****10% Material Over head :**	79019.15
Total :	1111010.65

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

Activity No : 30 **Activity Description :** HT Metering Structure at Consumer End

S.No	Materials Code	Materials Text	Item Catagory	Quantity	Unit	Rate in Rs.	Amount in Rs.
1	MST00029	RS Joist 150x150mm	Stock item	2,500.000	KG	71.98	179,950.00
2	INS30007	33KV Polymer Insulators (B&S)	Stock item	18	EA	486.68	8,760.24
3	HWR00004	33KV Metal parts(B&S)	Stock item	2	SET	245.13	490.26
4	FBR30001	33KV M.S.Back Clamps	Stock item	6	SET	283.92	1,703.52
5	ABS30004	33KV 800A D/B AB SWITCH WITH INSULATORS	Stock item	4	EA	52,514.53	210,058.12
6	CBX30001	33KV XLPE Cable 3 Core 400 Sq. mm	Stock item	80.000	M	3,841.22	307,297.60
7	SCB10114	33KV 3X400 Heat Shble out/d end ter kit	Stock item	4	EA	5,341.67	21,366.68
8	EMT00017	GI Earth Flat 25 mm x 3 mm	Stock item	150.000	KG	99.75	14,962.50
9	WRS00005	G.I. Wire 4mm (No.8)	Stock item	75.000	KG	86.26	6,469.50
10	ITR30061	33KV 1ph PTs,10 VA Burden 0.2 Class	Stock item	3	EA	24,086.59	72,259.77
11	LAS00004	33KV Lightning Arrestors Station Type	Stock item	3	EA	4,043.77	12,131.31
12	EMT00035	CI Earth Pipe 100 mm Dia 2.75 Mts Long	Stock item	3	EA	4,661.00	27,966.00
13	BRK30019	33KV 24V FED VCB WITH CTS & CR PANEL	Stock item	1	EA	494,522.38	494,522.38
14	BAT00075	24V 40AH Battery Charger(Conventional)	Stock item	1	EA	15,132.37	15,132.37
15	CDR00010	ACSR Conductor Panther	Stock item	100.000	M	245.63	24,563.00
16	MST00012	MS Channel 100x50 mm	Stock item	1,200.000	KG	66.79	80,148.00
17	CBP00006	LT PVC Cu Contr Cable 10 Core 2.5 Sq. mm	Stock item	200.000	M	254.30	50,860.00
18	CBP00002	LT PVC Cu Contr Cable 4 Core 2.5 Sq. mm	Stock item	100.000	M	101.37	10,137.00
19	CBP00001	LT PVC Cu Contr Cable 2 Core 2.5 Sq. mm	Stock item	100.000	M	61.52	6,152.00
20	MST00014	MS Flat 50x6 mm	Stock item	500.000	KG	75.09	37,545.00
21	MST00015	MS Flat 75x8	Stock item	200.000	KG	84.24	16,848.00
22	MHT30071	33KV HT TVR, 100/1A 0.2S 15min IP-Cat C	Stock item	1	EA	7,997.18	7,997.18
23	ITR30054	33KV Metering CT's 100/1A, 0.2S Class	Stock item	3	EA	17,035.60	51,106.80
						Material Cost	1,658,427.23

S.No	Services Code	Services Text	Item Catagory	Quantity	Unit	Rate in Rs.	Amount in Rs.

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

1	SWR11276	Erect-33KV DP Structure with RS Joist	-	4	SET	5,670.00	22,680.00
2	SWR10392	Erection of 33kv ABSwitch incl earthing	-	4	EA	4,500.00	18,000.00
3	SWR10396	Erect of 33kv LA stn type incl earthing	-	3	SET	880.00	2,640.00
4	SWR10399	Erection of 33kv CT s	-	3	SET	1,079.00	3,237.00
5	SWR10401	Erection of 33kv single phase PT s	-	3	SET	1,079.00	3,237.00
6	SWR10387	OD/Idoor end termination 33kv 3x400 xlpe	-	4	EA	2,764.76	11,059.04
7	SWR10357	ERECT. OF LINES-Providing of earthing	-	12	EA	1,234.20	14,810.40
8	SWR10394	Erect. of 33kv HG Fuseset incl earthing	-	1	SET	1,331.81	1,331.81
9	SWR10348	Erection of RS Joist 150 x 150 mm	-	8	EA	1,800.00	14,400.00
10	SWR10356	Mass concreting of supports incl. cement	-	8.000	M3	6,579.00	52,632.00
11	SWR10734	Con of Plinth HTTVR meter 0.6x0.3x0.9m	-	1	EA	5,202.00	5,202.00
12	SWR11119	Testing of HT TVR Meter at site	-	1	EA	246.00	246.00
13	SWR33447	PVC Casing 100mmx50mm height	-	1.000	M	325.00	325.00
14	SWR11771	Erect-24V Batery with Chrgr incl grot-SS	-	1	EA	1,050.00	1,050.00
15	SWR20685	Cement concrete with 40MM metal VCB plin	-	4.000	M3	5,160.00	20,640.00
16	SWR10460	Erection of 33kv VCB	-	1	EA	12,500.00	12,500.00
17	SMR11488	S-GI Bolts & Nuts,Washers etc.,	-	100.000	KG	117.50	11,750.00
18	SWR10921	Laying of earth mat,excavation 25x3mm	-	50	RMT	68.00	3,400.00
19	SMR40087	Sup TrollyMounted Co2 Cylinders(IS-2878)	-	2	EA	9,240.00	18,480.00
20	SWR23224	Excavate-Pit for 33KV VCB	-	1.000	M3	331.00	331.00
						Service Cost	217,951.25
						GST 18%	39,231.23
						3 % S & H Charges :	49512.90
						3 % Contingencies on materials:	49752.82
						10 % Estt. & General Charges :	165842.72
						****10% Material Over head :**	165842.72

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.

SOUTHERN POWER DISTRIBUTION COMPANY OF TS LIMITED

Estimate Number : E-2023-60-01-11-04-048

Total :	2346560.87

Copy to:

THE ASSISTANT ENGINEER/OPR/AE OP CHINNA SHANKA

THE ASSISTANT DIVISIONAL ENGINEER/OPERATION/MEDAK SUB-DIVIISON

THE DIVISIONAL ENGINEER/OPERATION/MEDAK DIVISION

THE SUPERINTENDING ENGINEER/OPERATION/MEDAK CIRCLE

THE CHIEF GENERAL MANAGER/OPERATION/RURAL ZONE

NOTE : 10 % Material Overhead Charges are Material Price Variation (MPV) Charges. These charges are for meeting abnormal changes in material cost only. This cost is not intended to be collected from the consumer and not included in determining delegation of powers.